N

FIRST LEVEL REFLECTED CEILING PLAN - ZONE 'D'

SCALE: 1/8" = 1'-0"

FIXTURE LEGEND

- RECESSED FLUORESCENT TROFFER (2'x4'/ 1'x4')
- FLUORESCENT INDUSTRIAL FIXTURE
- SURFACE MOUNTED FLUORESCENT FIXTURE
- PENDANT MOUNTED FLUORESCENT LIGHT FIXTURE
- RECESSED DOWNLIGHT
- EXIT SIGN / LIGHT
- SMOKE DETECTOR
- EXHAUST GRILLE
- SUPPLY DIFFUSER
- RETURN-AIR GRILLE
- SPEAKER
- PENDANT SPRINKLER HEAD (SEE MECHANICAL FOR TYPE)
- SIDEWALL SPRINKLER HEAD

CEILING LEGEND

- GYPSUM DRYWALL OR SYNTHETIC VENEER PLASTER CEILING/SOFFIT
- 24" x 48" SUSPENDED LAY-IN ACOUSTICAL CEILING
- 24" x 24" SUSPENDED LAY-IN ACOUSTICAL CEILING
- EXPOSED OR EXISTING CONSTRUCTION TO REMAIN

CEILING FINISH KEY
ROOM NAME AND NUMBER PLUS GENERAL CEILING FINISH AND HEIGHT UNLESS NOTED OTHERWISE BY FINISH KEY

FINISH KEY
SPECIFIC FINISH INFORMATION WHERE VARIED FROM CEILING FINISH KEY

CLASSROOM ← ROOM NAME
101 ← ROOM NUMBER
ACT ← CEILING FINISH ABBREVIATION (SEE BELOW) → ALUM
9'-0" ← CEILING HEIGHT (A.F.F.) → 8'-10"

CEILING FINISH ABBREVIATIONS

ACT	ACOUSTICAL LAY-IN CEILING TILE
ALUM	ALUMINUM PANEL
AWP	ACOUSTICAL WALL PANEL
AB	ACOUSTICAL BAFFLE
EX	EXISTING
EXP-P	EXPOSED CONSTRUCTION - TO BE PAINTED
FB	FABRIC BANNER
GYP-P	GYPSUM BOARD - TO BE PAINTED
GYP-EP	GYPSUM BOARD - TO BE EPOXY PAINTED
DEFS	POLYMER-BASED DIRECT APPLIED FINISH SYSTEM
LIN	LINEAR PVC SYSTEM
PT	PAINT
SVP	SYNTHETIC VENEER PLASTER
UF	(UNFINISHED)

NOTES

1. REFER TO FINISH PLANS FOR INFORMATION ON ROOM FINISHES.
2. REFER TO ARCHITECTURAL PLANS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION ON MATERIALS AND CONSTRUCTION.
3. WHERE EXPOSED CONSTRUCTION IS INDICATED TO BE PAINTED, THIS SHALL INCLUDE ALL STRUCTURAL MEMBERS, ROOF/FLOOR DECK, DUCTWORK, DIFFUSERS, GRILLES, PIPING, SUSPENDED EQUIPMENT, CONDUITS, ETC. (U.O.N.)

REFLECTED CEILING PLAN WALL LEGEND

(ALL WALLS INDICATED WITH LINE TYPES BELOW CONTINUE TO FLOOR OR ROOF STRUCTURE ABOVE - ALL WALLS WITHOUT THESE INDICATIONS EXTEND A MINIMUM OF 4" ABOVE THE HIGHEST ADJACENT CEILING)

- : 2-HOUR FIRE RATED HORIZONTAL EXIT
- : 2-HOUR FIRE BARRIER
- : SMOKE BARRIER WITH 1-HOUR FIRE RATING
- : SMOKE BARRIER (NON-RATED) UNENCLOSED FLOOR OPENINGS
- : 1-HOUR FIRE BARRIER FOR UNENCLOSED FLOOR OPENINGS
- : 1-HOUR FIRE BARRIER ENCLOSED VERTICAL SHAFTS
- : 1-HOUR FIRE BARRIER FOR PROTECTION FROM HAZARDS
- : SMOKE RESISTING PARTITION
- : NON RATED WALLS TO STRUCTURE ABOVE

REFLECTED CEILING PLAN GENERAL NOTES

1. REFER TO ELECTRICAL DRAWINGS FOR FIXTURE TYPES. REFER TO ELECTRICAL AND MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION PERTAINING TO ELECTRICAL AND MECHANICAL WORK.
2. COORDINATE SIZE AND LOCATION OF ALL ACCESS PANELS WITH TRADE REQUIRING THE SAME. ACCESS PANELS ARE SPECIFIED ARCHITECTURALLY BUT ARE REQUIRED TO BE PROVIDED BY TRADE. SPOT ALL LOCATIONS WITHIN FIXED GYPSUM BOARD CEILINGS AND RECEIVE APPROVAL FROM THE ARCHITECT'S FIELD REPRESENTATIVE BEFORE PLACEMENT.
3. COORDINATE CEILING SUSPENSION SYSTEMS WITH OTHER CEILING SPACE EQUIPMENT SUPPORTS.
4. ALL SMOKE BARRIER PARTITIONS, HORIZONTAL EXIT ENCLOSURES AND FIRE RATED PARTITIONS WHICH EXTEND TO THE DECK ABOVE SHALL BE MARKED EVERY 20'-0" HORIZONTALLY WITHIN THE CEILING SPACE: "FIRE AND SMOKE BARRIER - PROTECT ALL OPENINGS"
5. ALL GYPSUM BOARD FASCIAS @ SOFFITS, ADJACENT TO LAY-IN CEILINGS, SHALL EXTEND 4"MINIMUM ABOVE LAY-IN CEILINGS.
6. PROVIDE WOOD BLOCKING, ABOVE GYPSUM BOARD CEILINGS, AS REQUIRED FOR MISCELLANEOUS SUSPENDED ITEMS (e.g. CURTAIN TRACKS, WINDOW SHADES, ACOUSTICAL BAFFLES, ETC.)
7. REFER TO DRAWING A8.1 FOR TYPICAL DETAILS PERTAINING TO WALL TERMINATIONS AT STRUCTURE ABOVE.
8. REFER TO LIFE SAFETY PLANS FOR DAMPERING REQUIREMENTS

TMP ARCHITECTURE

TMP ARCHITECTURE INC
1191 WEST SQUARE LAKE ROAD
BLOOMFIELD HILLS - MICHIGAN - 48302
PH - 248.338.4561 FX - 248.338.0223
EM - INFO @TMP-ARCHITECTURE.COM

REGISTRATION SEAL

CONSULTANT

PROJECT TITLE
West Maple Elementary French School Remodeling

Birmingham Public Schools
Bloomfield Hills, Michigan

DRAWING TITLE
First Level
Reflected Ceiling Plan - Zone 'D'



KEYPLAN
NO SCALE

ISSUE DATES

12-04-17	BIDS
10-20-17	CD OWNER REVIEW
05.12.17	DD ESTIMATE
DATE:	ISSUED FOR:

DRAWN	AKW
CHECKED	JMM
APPROVED	JJC

PROJECT NO.
15104A

DRAWING NO.
A2.1D

Drawing File: Q:\cccad\2015\mep\15104a\15104a_ceil\15104a_a21d.dwg
Date: 04 , 2017 - 11:07:09am